BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer

SCHEDULE-B

NAME OF WORK: Providing Rain water Harvesting Facilities in Ward No 15 Dasarahalli Bagalagunte Sub Division

Sl. No	Description of work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as	cum	615.00	147.38	
2	Crushing of stone boulders of 150 mm size in an integrated stone crushing unit of 200 tonnes per hour capacity comprising of primary and secondary crushing units, belt conveyor and vibrating screens to obtain stone aggregates of 13.2 mm nominal size including cost of materials, equipments, labour etc. complete.	Cum	300.00	904.67	
3	Crushing of stone boulders of 150 mm size in an integrated stone crushing unit of 200 tonnes per hour capacity comprising of primary and secondary crushing units, belt conveyor and vibrating screens to obtain stone aggregates of 40 mm nominal size including cost of materials, equipments, labour etc. complete	Cum	150.00	812.84	
4	Crushing of stone boulders of 150 mm size in an integrated stone crushing unit of 200 tonnes per hour capacity comprising of primary and secondary crushing units, belt conveyor and vibrating screens to obtain stone aggregates of 20 mm nominal size including cost of materials, equipments, labour etc. complete	Cum	150.00	910.34	
5	Sand filling in wells complete as per drawing and technical specifications including cost of all materials, labour, HOM, form works, scaffolding & centering complete as per specifications.	Cum	75.00	3001.96	
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	810.00	74.65	

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,